

Lp.	Podst	Opis i wyliczenia	j.m.	Poszcz	Razem
1 ZADANIE 2					
1		Demontaż szafy w korytarzu głównym	kpl		
d.1		1	kpl	1.000	
				RAZEM	1.000
2	KNNR-W 3	Zerwanie posadzek - wykładziny	m ²		
d.1	0801-07	174.30	m ²	174.300	
				RAZEM	174.300
3	KNR 19-01	Wykucie z muru drzwi	m ²		
d.1	0358-04	2.12 <0.99*2.14>	m ²	2.120	
		2.12 <0.99*2.14>	m ²	2.120	
	korekta ob- miaru	-4.238	m ²	-4.238	
				RAZEM	0.002
4	KNP 4	Oderwanie listew przyciennych na ścianach rozbieranych	m		
d.1	0901.1-07	(6.25+2.98+14.12+4.55*2+10.65+9.82+3.44*2+3.40*2)*2	m	133.200	
		-(0.85+1.21+1.08+1.00*2+1.00*4+0.77+1.00)*2	m	-21.820	
				RAZEM	111.380
5	KNR 19-01	Wywóz gruzu spryzmowanego samochodami samowyladowczymi na odleg- łość do 1km	m ³		
d.1	0118-13	0.21 <4.24*0.05>	m ³	0.210	
		1.74 <174.30*0.01>	m ³	1.740	
	korekta ob- miaru	-1.955	m ³	-1.955	
				RAZEM	-0.005
6	KNR 19-01	Wywóz gruzu spryzmowanego samochodami samowyladowczymi - za każde dalsze 0,5km ponad 1km	m ³		
d.1	0118-14	Krotność = 18			
		0.21 <4.24*0.05>	m ³	0.210	
		1.74 <174.30*0.01>	m ³	1.740	
	korekta ob- miaru	-1.955	m ³	-1.955	
				RAZEM	-0.005
7		Oplata za utylizację i składowanie gruzu	t		
d.1		4.24*0.05*600.00/1000	t	0.127	
		174.30*10.00/1000	t	1.743	
				RAZEM	1.870
8		Renowacja drzwi i ościeżnic	m ²		
d.1		1.00*2.14+1.00*2.14+1.00*2.14+1.00*2.18+1.00*2.14+0.77*2.02+1.00*2.14*3+ 0.85*2.00	m ²	20.415	
				RAZEM	20.415
9	KNR 4-01	Zeskrobanie i zmycie starej farby w pomieszczeniach o powierzchni podłogi ponad 5m2	m ²		
d.1	1202-09	21.75*4.09-0.99*2.14	m ²	86.839	
	pom.152	18.45*4.09-0.99*2.14*2-0.90*2.00	m ²	69.423	
	pom.152a	25.85*4.09-0.99*2.14	m ²	103.608	
	pom.130	19.90*3.42-0.97*2.20-1.48*2.85	m ²	61.706	
	pom.131	13.95*3.42-1.00*2.14-1.46*2.95	m ²	41.262	
	pom.131A	13.42*3.42-1.00*2.14-1.47*2.95	m ²	39.420	
	pom.132	13.80*3.42-1.00*2.14-1.47*2.95	m ²	40.720	
	pom.133A	12.50*3.42-1.00*2.18-1.45*2.94-1.00*2.00	m ²	34.307	
	pom.133	13.54*3.42-1.00*2.14-0.77*2.02-1.00*2.18-1.46*2.93	m ²	36.154	
	pom.133B	14.14*3.42-0.77*2.20-1.46*2.95*2	m ²	38.051	
	pom.134	16.04*3.42-1.00*2.14-1.46*2.94	m ²	48.424	
	pom.135	16.00*3.42-1.00*2.14-1.46*2.92	m ²	48.317	
	pom.136	16.42*3.42-0.79*2.00-1.46*2.92	m ²	50.313	
	pom.137	(8.16+12.75)*3.42-1.45*2.94-1.21*2.00*2-1.08*2.20-0.79*2.00-0.85*2.00	m ²	56.753	
	pom.138	19.47*3.42-1.45*2.93-1.46*2.93*2	m ²	53.783	
		19.80*4.07-0.97*2.20-1.08*2.20-1.35*3.08	m ²	71.918	
		31.25*3.42-1.08*2.20-1.00*2.14*7	m ²	89.519	
				RAZEM	970.517
10	KNR 2-02s	Drzwi DR6 wym.2,16(1,08+1,08)*2,45m EIS30 przeszklone, samozamykacz RKZ i trzymacze elektromagnetyczne, oadająca uszczelka dymoszczelna	m ²		
d.1	1203-01	2.16*2.45*2	m ²	10.584	
				RAZEM	10.584
11	KNR 2-02	Okladziny ścian pojedyncze z płyt gipsowo-kartonowych (suche tynki gipsowe) na zaprawie na paskach	m ²		
d.1	2006-02	(6.25+2.98+14.12+4.55*2+10.65+9.82+3.44*2+3.40*2)*3.42*2	m ²	455.544	
		-(0.85*2.00+1.21*2.00+1.08*2.20+1.00*2.14*2+1.00*2.14*4+0.77*2.02+1.00* 2.18)*2	m ²	-46.143	

Lp.	Podst	Opis i wyliczenia	j.m.	Poszcz	Razem
				RAZEM	409.401
12 d.1	KNR 2-02 2009-02	Tynki (gładzie) jednowarstwowe wewnętrzne ścian o podłożu z tynku z gipsu szpachlowego wykonywane ręcznie grubości 3mm	m ²		
	pom.152	21.75*4.09-0.99*2.14	m ²	86.839	
	pom.152	18.45*4.09-0.99*2.14*2-0.90*2.00	m ²	69.423	
	pom.152a	25.85*4.09-0.99*2.14	m ²	103.608	
	pom.130	19.90*3.42-0.97*2.20-1.48*2.85	m ²	61.706	
	pom.131	13.95*3.42-1.00*2.14-1.46*2.95	m ²	41.262	
	pom.131A	13.42*3.42-1.00*2.14-1.47*2.95	m ²	39.420	
	pom.132	13.80*3.42-1.00*2.14-1.47*2.95	m ²	40.720	
	pom.133A	12.50*3.42-1.00*2.18-1.45*2.94-1.00*2.00	m ²	34.307	
	pom.133	13.54*3.42-1.00*2.14-0.77*2.02-1.00*2.18-1.46*2.93	m ²	36.154	
	pom.133B	14.14*3.42-0.77*2.20-1.46*2.95*2	m ²	38.051	
	pom.134	16.04*3.42-1.00*2.14-1.46*2.94	m ²	48.424	
	pom.135	16.00*3.42-1.00*2.14-1.46*2.92	m ²	48.317	
	pom.136	16.42*3.42-0.79*2.00-1.46*2.92	m ²	50.313	
	pom.137	(8.16+12.75)*3.42-1.45*2.94-1.21*2.00*2-1.08*2.20-0.79*2.00-0.85*2.00	m ²	56.753	
	pom.138	19.47*3.42-1.45*2.93-1.46*2.93*2	m ²	53.783	
		19.80*4.07-0.97*2.20-1.08*2.20-1.35*3.08	m ²	71.918	
		31.25*3.42-1.08*2.20-1.00*2.14*7	m ²	89.519	
				RAZEM	970.517
13 d.1	KNR 2-02 1505-03	Dwukrotne malowanie farbami emulsyjnymi wewnętrznych podłoży gipsowych z gruntowaniem - ściany istniejące	m ²		
	pom.152	21.75*4.09-0.99*2.14	m ²	86.839	
	pom.152	18.45*4.09-0.99*2.14*2-0.90*2.00	m ²	69.423	
	pom.152a	25.85*4.09-0.99*2.14	m ²	103.608	
	pom.130	19.90*3.42-0.97*2.20-1.48*2.85	m ²	61.706	
	pom.131	13.95*3.42-1.00*2.14-1.46*2.95	m ²	41.262	
	pom.131A	13.42*3.42-1.00*2.14-1.47*2.95	m ²	39.420	
	pom.132	13.80*3.42-1.00*2.14-1.47*2.95	m ²	40.720	
	pom.133A	12.50*3.42-1.00*2.18-1.45*2.94-1.00*2.00	m ²	34.307	
	pom.133	13.54*3.42-1.00*2.14-0.77*2.02-1.00*2.18-1.46*2.93	m ²	36.154	
	pom.133B	14.14*3.42-0.77*2.20-1.46*2.95*2	m ²	38.051	
	pom.134	16.04*3.42-1.00*2.14-1.46*2.94	m ²	48.424	
	pom.135	16.00*3.42-1.00*2.14-1.46*2.92	m ²	48.317	
	pom.136	16.42*3.42-0.79*2.00-1.46*2.92	m ²	50.313	
	pom.137	(8.16+12.75)*3.42-1.45*2.94-1.21*2.00*2-1.08*2.20-0.79*2.00-0.85*2.00	m ²	56.753	
	pom.138	19.47*3.42-1.45*2.93-1.46*2.93*2	m ²	53.783	
		19.80*4.07-0.97*2.20-1.08*2.20-1.35*3.08	m ²	71.918	
		31.25*3.42-1.08*2.20-1.00*2.14*7	m ²	89.519	
				RAZEM	970.517
14 d.1	KNR 2-02 1118-01	Przygotowanie podłoża pod posadzki	m ²		
		174.30	m ²	174.300	
				RAZEM	174.300
15 d.1	KNR 2-02 1113-02	Posadzki z tworzyw sztucznych typy tarkett	m ²		
		174.30	m ²	174.300	
				RAZEM	174.300
16 d.1	KNKRB 2 1106-06	Ponowny montaż listew przyściennych - z demontażu	m		
		(6.25+2.98+14.12+4.55*2+10.65+9.82+3.44*2+3.40*2)*2	m	133.200	
		-(0.85+1.21+1.08+1.00*2+1.00*4+0.77+1.00)*2	m	-21.820	
				RAZEM	111.380