

Lp.	Podst	Opis i wyliczenia	j.m.	Poszcz	Razem
15 d.1	KNR 2-02s 1203-01	Drzwi DR11 EI30 1.12*2.19	m ² m ²	 2.453	
				RAZEM	2.453
16 d.1	KNR 2-02s 1203-01	Drzwi DR12 EI60 1.09*2.18	m ² m ²	 2.376	
				RAZEM	2.376
17 d.1	KNR 2-02s 1203-01	Drzwi DR13 EI60 1.10*2.18	m ² m ²	 2.398	
				RAZEM	2.398
18 d.1	KNR 2-02s 1203-01	Drzwi DR14 EI30 1.80*2.00	m ² m ²	 3.600	
				RAZEM	3.600
19 d.1	KNR 2-02s 1203-01	Drzwi DR15 EI60 1.10*2.02	m ² m ²	 2.222	
				RAZEM	2.222
20 d.1	KNR 2-02 2003-04	Ścianki działowe z płyt gipsowo-kartonowych GKF na rusztach metalowych pojedynczych z pokryciem obustronnym, dwuwarstwowo 0.90*2.00*2 2.22*(2.00+2.42)/2-1.80*2.00 1.94*2.40-0.90*1.96 2.58*(1.75+1.92)/2	m ² m ² m ² m ²	 3.600 1.306 2.892 4.734	
				RAZEM	12.532
21 d.1	KNR 2-02 0613-06	Izolacje cieplne i przeciwdźwiękowe pionowe z płyt z wełny mineralnej gr.70mm układanych na sucho 0.90*2.00*2 2.22*(2.00+2.42)/2-1.80*2.00 1.94*2.40-0.90*1.96 2.58*(1.75+1.92)/2	m ² m ² m ² m ²	 3.600 1.306 2.892 4.734	
				RAZEM	12.532
22 d.1	KNR 2-02 2009-02	Tynki (gładzie) jednowarstwowe wewnętrzne ścian o podłożu z tynku z gipsu szpachlowego wykonywane ręcznie grubości 3mm 12.532*2	m ² m ²	 25.064	
				RAZEM	25.064
23 d.1	KNR 2-02 1505-03	Dwukrotne malowanie farbami emulsyjnymi wewnętrznych podłoży gipsowych z gruntowaniem 12.532*2	m ² m ²	 25.064	
				RAZEM	25.064

Lp.	Podst	Opis i wyliczenia	j.m.	Poszcz	Razem
1	ZADANIE 6				
1	KNR 19-01	Wykucie z muru ościeżnic o powierzchni powyżej 2m2	m ²		
d.1	0358-04				
		1.85 <0.90*2.05>	m ²	1.850	
		1.83 <0.89*2.06>	m ²	1.830	
		2.87 <1.44*1.99>	m ²	2.870	
		0.85*2.00	m ²	1.700	
		1.87 <1.01*1.85>	m ²	1.870	
		2.06 <1.06*1.94>	m ²	2.060	
		0.88*2.00	m ²	1.760	
		3.8 <1.94*1.96>	m ²	3.800	
		2.22 <1.10*2.02>	m ²	2.220	
		1.85 <0.95*1.95>	m ²	1.850	
		2.45 <1.12*2.19>	m ²	2.450	
		7.13 <1.09*2.18*3>	m ²	7.130	
		2.4 <1.10*2.18>	m ²	2.400	
	korekta ob- miaru	-30.326	m ²	-30.326	
				RAZEM	3.464
2	KNR 19-01	Wywóz gruzu spryzmowanego samochodami samowyladowczymi na odleg- łość do 1km	m ³		
d.1	0118-13	33.79*0.05	m ³	1.690	
				RAZEM	1.690
3	KNR 19-01	Wywóz gruzu spryzmowanego samochodami samowyladowczymi - za każde dalsze 0,5km ponad 1km	m ³		
d.1	0118-14	Krotność = 18 33.79*0.05	m ³	1.690	
				RAZEM	1.690
4		Oplata za utylizację i składowanie gruzu	t		
d.1		1.01 <1.69*600.00/1000>	t	1.010	
	korekta ob- miaru	-1.014	t	-1.014	
				RAZEM	-0.004
5	KNR 2-02s	Drzwi DR1 EI30	m ²		
d.1	1203-01	0.90*2.00	m ²	1.800	
				RAZEM	1.800
6	KNR 2-02s	Drzwi DR2 EI30	m ²		
d.1	1203-01	0.80*2.00	m ²	1.600	
				RAZEM	1.600
7	KNR 2-02s	Drzwi DR3 EI30	m ²		
d.1	1203-01	1.44*1.99	m ²	2.866	
				RAZEM	2.866
8	KNR 2-02s	Drzwi DR4 EI60	m ²		
d.1	1203-01	0.85*2.00	m ²	1.700	
				RAZEM	1.700
9	KNR 2-02s	Drzwi DR5 EI30	m ²		
d.1	1203-01	1.00*1.80	m ²	1.800	
				RAZEM	1.800
10	KNR 2-02s	Drzwi DR6 EI30	m ²		
d.1	1203-01	1.06*1.94	m ²	2.056	
				RAZEM	2.056
11	KNR 2-02s	Drzwi DR7 EI30	m ²		
d.1	1203-01	0.80*2.00	m ²	1.600	
				RAZEM	1.600
12	KNR 2-02s	Drzwi DR8 EI60	m ²		
d.1	1203-01	0.90*1.96	m ²	1.764	
				RAZEM	1.764
13	KNR 2-02s	Drzwi DR9 EI30	m ²		
d.1	1203-01	0.80*2.00	m ²	1.600	
				RAZEM	1.600
14	KNR 2-02s	Drzwi DR10 EI60	m ²		
d.1	1203-01	0.95*1.95	m ²	1.853	
				RAZEM	1.853